Bill of Materials (BOM)

Project: Electrical Control Panel for Industrial Machines

Item No.	Decription	Specification	Qty	Unit
1	Main MCCB	63 A, 4P, 415V	1	pcs
2	MCB for Machine A	20 A, 3P, 415V	1	pcs
3	MCB for Machine B	10 A, 3P, 415V	1	pcs
4	MCB for Mschine C	16A, 1P, 230V	1	pcs
5	RCD for Machine C	30 mA, 2P, 230V	1	pcs
6	Contactor for Machine A	AC-3, 12 A, 415V	1	pcs
7	Overload Relay for Machine A	8-12 A adjustable	1	pcs
8	Contactor for Machine B	AC-3, 9 A, 415V	1	pcs
9	Overload Relay for Machine B	3-5 A adjustable	1	pcs
10	Cable For Machine A	Cu, 2.5 mm^2, 3-core	15	m
11	Cable For Machine B	Cu, 1.5 mm^2, 3-core	10	m
12	Cable For Machine C	Cu, 2.5 mm^2, 3-core	20	m
13	Distribution Board Enclosure	Metal, 6-8 way, IP54	1	pcs
14	Terminal Blocks	DIN rail type	10	pcs
15	Earth Busbar	Copper, insulated	1	pcs

REFERENCE EXTERNE - quantites et caracteristiques a verifier